

Project Profile

Moat Renovation, Council House, College Green, Bristol

Client :	Bristol City Council
Value :	£150k
Duration:	15 weeks
Our Role:	Principal Contractor

This renovation project in front of one of Bristol's most visually impressive buildings, Grade II* Listed, was undertaken essentially to put a halt to any further deterioration.

The surface area of the moat is a massive 140 metres long by 10 metres wide and works initially commenced with the erection of scaffolding to support a huge 3m high tent. This procedure ensured that the moat, once drained of water, remained entirely dry for the duration of the contract.

Once the tent was secured skilled operatives undertook repairs to all existing brickwork and layered the interior of the moat with grey glass-reinforced plastic to 4mm thick to create a new lining.

These works were programmed during the Autumn season for two reasons. One, as the water in the moat is used as a coolant for the Council House's air conditioning system and two, to ensure that summer visitors were able to enjoy the moat and fountains.



Contact Details



E R Hemmings (Building) Ltd • Dean Road • Yate • Bristol • BS37 5NR

Tel: 01454 884444 • Fax: 01454 884455 • www.erh.co.uk • Email: mail@erh.co.uk